

PROJECT #LPB49520

Project consists of isolated shell and core improvements to the downtown Macy's building.

PROPOSED SCOPE OF WORK SUMMARY

Level 1 Common Area

ITEM 1. INTERIOR: Construct demising walls to subdivide Level 1 space between tenants and common area.

ITEM 2. INTERIOR: Introduce new ceiling finish elements at Level 1 to define new main entry and common area.

ITEM 3. EXTERIOR: Replace existing door assembly within existing opening at Entry 2.5 to create new main entry statement.

ITEM 4. EXTERIOR: Modify existing marque canopy roof to provide illumination at Entry 2.5 and 8. **ITEM 5. EXTERIOR:** Attach new blade sign cabinets to existing marquee canopy for future tenant signage.

Venue Tenant

ITEM 6. EXTERIOR: Attach Venue signage to West Elevation.

ITEM 7. EXTERIOR: Reconfigure Entry 9 within existing opening to replace existing doors with new service doors and one pair of egress doors.

Tenant A

ITEM 8. INTERIOR: Remove a portion of L1 ceiling for new retail mezzanine level within the tenant space. Remove portions of the slab to create a vertical connection to Level 2 lease area within the tenant space.

ITEM 9. EXTERIOR: Replace portion of existing display window with new pair of solid egress doors to serve code-required reconfiguration of Stair 2 exit path from Basement and occupancies. **ITEM 10. EXTERIOR:** Replace existing Entry 2 with glass display window within existing opening.

Tenant (

ITEM 11. EXTERIOR: Replace existing Entry 5 with one glass egress door and a new glass display window within existing opening.

Tenant E

ITEM 12. EXTERIOR: Reopen previously sealed Entry 8.5.


SUMMARY OF LANDMARK CONTROLLED ITEMS PER LANDMARKS ORDINANCE 114772:


- Exterior of the building including roof and marquee
- Decorative ornament of first floor ceiling and columns
- Elevator wall surrounds
- 2 Sets of stair railings located on the first floor




3rd & Pine Redevelopment Project

21 DEC 2020














300 Pine











300 Pine





ITEM 1. INTERIOR: Construct demising walls to subdivide Level 1 space between tenants and common area.

SCOPE OF WORK

- -Provide new Level 1 "Venue," separated by a 2-hour fire rated wall.
- -Provide new unrated demising walls to delineate Tenants A, B, and C from the Common Area and Entry 2.5.
- -Install new decorative trim false beam work as noted.







NOTE

*HISTORIC DECORATIVE PLASTER: HEMP FIBER BINDER & PLASTER.

NEW DECORATIVE PLASTER
WORK TO BE FORMED FROM
MOLDS MADE FROM THE
EXISTING HISTORIC TRIM AND
CAPITAL, COMPOSED OF THE
SAME MATERIALS & FINISHED TO
MATCH EXISTING HISTORICAL
ELEMENTS.






__ EXISTING HISTORIC
DECORATIVE PLASTER TRIM AT
FALSE BEAMS*.
SEE NOTE ABOVE.


EXISTING HISTORIC DECORATIVE PLASTER COLUMN CAPITAL*. SEE NOTE ABOVE.


EXISTING COLUMN SHAFT.

DIRECT APPLIED PLASTER
TO CONCRETE COLUMN.

3rd & Pine Redevelopment Project 21 DEC 2020








Detail 01-

Existing Condition


Plan View



Existing decorative trim and false beam work on this area to be saw-cut and removed to allow installation of new fire rated demising walls

Detail 01-

Proposed Section Detail





K-13 acoustical spray. Paint color Charcoal Gray

New tenant 2 HR demising wall assembly

Existing decorative trim to remain, repair and refurbish as required to match existing


Section A -Proposed Detail





Detail 02-Existing Condition

Plan View




Existing column to remain


Existing decorative trim and false beam work on this area to be removed to allow installation of new fire rated demising walls

New plaster coffer replicated to match existing to complete the grid


Existing decorative trim to remain, repair and refurbish as required to match existing.

New tenant 2 HR demising wall





Detail 02-Proposed Section Detail





Existing decorative trim to remain, repair and refurbish as required to match existing.

Unistrut curtain hangers or other elements to be installed clear of the existing coffers

Existing decorative column capital to remain and be protected during new work.

New tenant 2 HR demising wall assembly







Venue

300 Pine

Detail 03-**Existing Condition** Existing column to remain Plan View Existing decorative trim and false beam work on this area to be removed to allow installation of new fire rated demising walls New plaster coffer replicated to match existing to Detail 03complete the grid **Proposed RCP** New tenant 2 HR demising wall Plan View Existing decorative trim to remain, repair and refurbish as required to match existing.


Tenant Area





Venue

Venue





Existing decorative trim to remain, repair and refurbish as required to match existing.


Unistrut curtain hangers or other elements to stay clear of the existing coffers


Existing decorative column capital to remain and be protected during new work.

New tenant 2 HR demising wall assembly












Section D @ GRID 7-Proposed





Detail 05-Existing Condition


Plan View




Existing decorative trim and false beam work on this area to be saw-cut and removed to allow installation of new fire rated demising walls

Detail 05-Proposed


Plan View




Detail 05-Proposed Section Detail Section View



Enlarged Interior Section Elevation








ITEM 2. INTERIOR: Introduce new ceiling finish elements at Level 1 to define new main entry and common area.

300 Pine






300 Pine

Existing historic coffers and column capitals to remain






Proposed Portal Entrance Item 2A

Proposed Common Area Item 2B Illuminated ceiling element introduced between historic decorative coffers Existing ceiling above




remains intact


Proposed Portal Entrance Illustrative View



4TH AVE




CALLISONTKL




Detail 01 Metal Panel Ceiling Sample Detail Existing concrete slab beams Existing decorative trim to remain Ceiling frame module, **Elevation varies** MECHANICAL MEZZANINE " Attach suspension wires and framing to existing deck Sprinkler piping and heads run between ceiling frame and modules 3RD AVE

4TH AVE







Existing concrete slab & beams


New suspended gypsum ceiling

Reveal for lighting and linear diffuser

Existing decorative trim to remain

Existing column capital to remain and be protected as feasible

Detail 03 @ Grid 6



Existing concrete slab & beams

Sawcut and remove existing flat ceiling


Reveal and suspension point for lighting

New suspended grid cloud ceiling with translucent acrylic panels

Existing decorative trim to remain

Existing column capital to remain and to be protected as feasible

Lighting to illuminate planting




4TH AVE



ITEM 3. EXTERIOR: Replace existing door assembly at Entry 2.5 to create new main entry statement.











Existing Previously Approved Entry 2.5

Proposed Entry 2.5








DETAIL 01


Portal to Existing Stone Jamb

Plan View



SECTION A Detail Entry Door


Section View



SECTION B

Detail Entry Door

Section View









ITEM 4. EXTERIOR: Modify existing marque canopy roof to provide illumination.

SCOPE OF WORK

- Remove existing roof metal plate and replacing with translucent panel and lighting assembly within existing marquee canopy structure at Entry 2.5 and Entry 8








Existing Canopy at Entry 2.5



Existing Canopy at Entry 2.5

3rd & Pine Redevelopment Project

21 DEC 2020




Existing Canopy at Entry 2.5




Existing Canopy at Entry 8

Existing Canopy Canopy Renovation Summary & Details




DETAIL 01

Tee Flange Corrosion Repair



DETAIL 03


Ledger Replacement



- CUTTER LINER AS REQUIRED. 2. REMOVE ANY EXISTING THE
- TO LEDGER CONNECTION BOLTS. 3. SEPARATE TEE FROM LEDGER
 AS REQUIRED.
- GRIND BEARING SURFACES ON TEE AND LEDGER DOWN UNTIL FREE OF CORRODED WATERIAL.
- REMOVE ADJACENT FILER BAR EACH SIDE OF THE CRIMO LEDGER FREE OF CORROGED WATERAL. REPLACE FILLER BAR WITH MATERIAL TO MATCH EXISTING.
- RE-COMMECT TEE TO LEDGER WITH NEW BOLTS OR OPTIONAL WELDS AS SHOWN.
- 7. RE-INSTALL DECKING.

DETAIL 02


Tee to Ledger Conn Repair



DETAIL 04

Typ Deck Plan Replacement

3RD AVE



4TH AVE

300 Pine

Seattle, WA




CALLISONRTKL




Proposed canopy at Entry 2.5


3rd & Pine Redevelopment Project 21 DEC 2020




Proposed canopy at Entry 8.5



Plan View



300 Pine






COMMON AREA

ITEM 5. EXTERIOR: Attach new blade sign cabinets to existing marquee canopy for future tenant signage.



3RD AVENUE





EXISTING PINE ST EXTERIOR BLADE SIGNAGE CABINET FOR REFERENCE.



3RD AVE PROPOSED NEW BLADE SIGNAGE CABINET TO MATCH **EXISTING CABINET DIMENSIONS, FINISHES AND ATTACHMENT** DETAIL.



4TH AVE PROPOSED NEW BLADE SIGNAGE CABINETS TO MATCH EXISTING CABINET DIMENSIONS, FINISHES AND ATTACHMENT DETAIL.



OLIVE WAY PROPOSED NEW BLADE SIGNAGE CABINET TO MATCH EXISTING CABINET DIMENSIONS, FINISHES AND ATTACHMENT DETAIL.

CALLISONTKL

3rd & Pine Redevelopment Project

21 DEC 2020



TRANSLUCENT WHITE POLYCARBONATE FACE W/ PLOTTER CUT MATTE BLACK VINYL GRAPHICS, APPLIED DIRECT TO FIRST - SURFACE, INSTALL INTO EXISTING CABINET,


CONFIRM FINAL SIZE OF FACE BEFORE FINAL PRODUCTION



VENUE TENANT ITEM 6. EXTERIOR: Attach Venue signage to West Elevation.

SCOPE OF WORK


- Modify Windows to Receive Signage Connection to Building
- Provide Supporting Structure for Canopy Through Window Opening to Building Structure
- Install New Marquee and Associated Structural and Electrical Connections






Existing Windows to Be Removed and Stored.

Infill Window Openings with Dark Bronze Metal Panel




4TH AVE



Existing Windows behind to Be Removed and Stored. **Protect and Preserve** Surrounding Sills. Install New Infill Panels

Preserve and Protect **Existing Canopy to** Remain

Existing Storefront Doors Removed. Approval for Replacement **Obtained Under** Previous Submittal.



SIGN 1: NEW WALL MOUNTED MARQUEE SIGN MANUFACTURE AND INSTALL ONE (1) NEW MARQUEE SIGN


- 1) CORRUGATED ALUMINUM PANEL AND W/ SQ TUBE FRAMING. PAINT METALLIC GOLD, SATIN FINISH. UP-LIT WITH WARM WHITE LEDS.
- (2) 6" DEEP, FABRICATED ALUMINUM LETTERS WITH RECESSED FACES. PAINT RETURNS DARK METALLIC GOLD. FACES SATIN WHITE. LIT WITH 6500K WHITE EXPOSED NEON TUBING MOUNTED GLASS SUPPORTS
- (3) FABRICATED ALUMINUM SIGN CABINET PAINTED METALLIC MAGENTA AND TEAL COLORS, SATIN FINISH. LIT WITH 15MM BUBBLE GUM PINK AND AQUA NEON TUBING MOUNTED WITH GLASS SUPPORTS.

Signage Structure Plan Detail @ Level 2

- (3) FABRICATED ALUMINUM SIGN CABINET PAINTED METALLIC MAGENTA AND TEAL COLORS, SATIN FINISH. LIT WITH 15MM BUBBLE GUM PINK AND AQUA NEON TUBING MOUNTED WITH GLASS SUPPORTS.
- (4) S11 LED MARQUEE BULBS
- (5) WHITE POLY CARBONATE READERBOARD SIGN FACE WITH THERMOFORMED PLASTIC MARQUEE LETTERING (6" SHOWN) AND MOUNTING GRID AS NEEDED. FACES HELD IN PLACE WITH 2" ALUMINUM RETAINERS PAINTED SATIN BLACK. BACK-LIT WITH 5000K WHITE LEDS.
- (6) FABRICATED ALUMINUM COLUMN SHAPE PAINTED METALLIC GOLD, MAGENTA, AND TEAL COLORS, SATIN FINISH, 15MM WARM WHITE, SUNFLOWER YELLOW, AND AQUA NEON TUBING MOUNTED WITH GLASS SUPPPORTS.
- 7 DEDICATED SIGN CIRCUIT(S) 120V 20A, NUMBER OF CIRCUITS REQUIRED TBD.
- (8) HSS STRUCTURAL SUPPORTS MOUNT SIGN TO BUILDING. (TBD BASED ON SITE SURVEY).
- (9) APPROXIMATE PERIMETER OF CANOPY BELOW SIGN



21 DEC 2020






VENUE TENANT

ITEM 7. EXTERIOR: Reconfigure Entry 9 to replace existing doors with new service doors and one pair of egress doors.











300 Pine







3rd & Pine Redevelopment Project

21 DEC 2020







21 DEC 2020

DISPLAY WINDOW

PROPOSED ENTRY-09

1/8" = 1'-0"

36"

Extent of existing opening


maintained



TENANT A


ITEM 8. INTERIOR: Remove a portion of L1 ceiling coffers to provide adequate headroom for new retail mezzanine level within the tenant space. Cut new openings in L2 slab to create a vertical connection to Level 2 lease area within the tenant space.

300 Pine




PROPOSED BUILDING SECTION

Section drawing showing new mezzanine floors with impact of existing decorative coffer to maximum clear height



EXISTING BUILDING SECTION




300 Pine




TENANT A

ITEM 9. EXTERIOR: Replace portion of existing display window with new pair of solid egress doors to serve code-required reconfiguration of Stair 2 exit path from Basement and SubBasement occupancies.








300 Pine









1/8" = 1'-0"



PLAN - EXISTING EGRESS EXIT

1/8" = 1'-0"





PLAN - PROPOSED EGRESS EXIT


1/8" = 1'-0"





TENANT A
ITEM 10. EXTERIOR: Replace existing Entry 2 with glass display window.








CALLISONTKL

300 Pine






VESTIBULE. WHERE OCCURS. SEE GROUND FLOOR PLAN. **VESTIBULE** UNDER SEPARATE PERMIT

PREVIOUSLY APPROVED **ENTRY DOORS**

CODE COMPLIANT (4) DOOR LEAF 42" W X 7'-0"H CONTINUOUS ROTON HINGE. **INSULATED GLASS PANELS**



PLAN - EXISTING APPROVED ENTRY

EXISTING PREVIOUSLY APPROVED ENTRY-02


1/8" = 1'-0"



RECONFIGURED WINDOW ASSEMBLY

KAWNER 250. DARK BRONZE FRAME STOREFRONT ASSEMBLY 42" W X 7'-0"H

84" W X 7'-0"H



PLAN - PROPOSED DISPLAY WINDOW



3rd & Pine Redevelopment Project 21 DEC 2020

300 Pine Seattle, WA




COMPARATIVE ENTRY STUDY EAST ELEVATION - EXISTING & PROPOSED




TENANT C

ITEM 11. EXTERIOR: Replace existing Entry 5 with one glass egress door and a new glass display window.










EXISTING PREVIOUSLY APPROVED ENTRY-05

1/8" = 1'-0"



PROPOSED EXIT AND DSPLAY WINDOW-05

1/8" = 1'-0"

VESTIBULE. WHERE OCCURS. SEE GROUND FLOOR PLAN EXISTING ENTRY DOORS. (4) DOOR LEAF 42" W X 7'-0" H

PROPERTY LINE (AVERAGE LOCATION)

OUTSIDE


INSIDE

PLAN - EXISTING APPROVED ENTRY

1/8" = 1'-0"

INSIDE


RECONFIGURED EXIT &
DISPLAY WINDOW
(1) DOOR LEAF
42" W X 7'-0"H



PROPERTY LINE (AVERAGE LOCATION)

PLAN - PROPOSED EXIT AND DISPLAY WINDOW


1/8" = 1'-0"




3rd & Pine Redevelopment Project 300 Pine 21 DEC 2020 Seattle, WA

















300 Pine










PLAN - EXISTING PREVIOUSLY SEALED ENTRY

1/8" = 1'-0"


EXISTING CONDITION

1/8" = 1'-0"



RECONFIGURED ENTRY DOORS

(2) DOOR LEAF 30" W X 7'-0"H



PROPERTY LINE (AVERAGE LOCATION)

PLAN - PROPOSED ENTRY

1/8" = 1'-0"

